

Annual Concrete Work (#8893485)

Owner: Baytown TX, City of

Solicitor: Baytown TX, City of

01/03/2024 02:00 PM CST

						Teamwork Construction Services, Inc.		Valtex Construction Services	
Section Title	Line Item	Item Description	UofM	QTY	Unit Price	Extension	Unit Price	Extension	
4 inch Existing Sidewalk							\$456.00		\$855.00
	1	Remove, dispose, and replace existing concrete sidewalks, projects of 0-50 square yards, per specifications	SY	1	\$149.00	\$149.00	\$165.00	\$165.00	
	2	Remove, dispose, and replace existing concrete sidewalks, projects of 51-200 square yards, per specifications	SY	1	\$120.00	\$120.00	\$200.00	\$200.00	
	3	Remove, dispose, and replace existing concrete sidewalks, projects of 201-1000 square yards, per specifications	SY	1	\$96.00	\$96.00	\$240.00	\$240.00	
	4	Remove, dispose, and replace existing concrete sidewalks, projects over 1000 square yards, per specifications	SY	1	\$91.00	\$91.00	\$250.00	\$250.00	
New 4 inch Sidewalk							\$424.00		\$630.00
	5	Construct new 4" concrete sidewalk with headers, dowels, expansion joints, excavation and disposal of existing soil, projects of 0-50 square yards, per specifications	SY	1	\$144.00	\$144.00	\$140.00	\$140.00	
	6	Construct new 4" concrete sidewalk with headers, dowels, expansion joints, excavation and disposal of existing soil, projects of 50-200 square yards, per specifications	SY	1	\$114.00	\$114.00	\$145.00	\$145.00	
	7	Construct new 4" concrete sidewalk with headers, dowels, expansion joints, excavation and disposal of existing soil, projects of 201-1000 square yards, per specifications	SY	1	\$91.00	\$91.00	\$150.00	\$150.00	
	8	Construct new 4" concrete sidewalk with headers, dowels, expansion joints, excavation and disposal of existing soil, projects over 1000 square yards, per specifications	SY	1	\$75.00	\$75.00	\$195.00	\$195.00	
Curb and Gutter							\$516.00		\$1,569.00
	9	Construct new 5" concrete sidewalk with headers, dowels, expansion joints, excavation and disposal of existing soil, all projects 0-1000+ square yards, per specifications	SY	1	\$157.00	\$157.00	\$305.00	\$305.00	
	10	Sod-provide and install City recommended sod, per specifications	SY	1	\$19.00	\$19.00	\$120.00	\$120.00	
	11	Remove, dispose, replace existing 6" concrete driveway, base repair with 6" of 1-1/2 sack cement stabilized sand, per specifications	SY	1	\$130.00	\$130.00	\$298.00	\$298.00	
	12	Remove, dispose, replace existing concrete curb and gutter with 6" of 1-1/2 sack cement stabilized sand, per specifications	LF	1	\$98.00	\$98.00	\$431.00	\$431.00	

Construct new concrete curb and gutter with 6" of 1-1/2 sack cement						
13 stabilized sand, per specifications	LF	1	\$82.00	\$82.00	\$360.00	\$360.00
14 Construct new dowweled-on concrete curb, all types, per	LF	1	\$30.00	\$30.00	\$55.00	\$55.00
Full Depth Repair of 7 Inch Concrete Pavement				\$294.00		\$505.00
Removal, disposal, replacement of concrete and material, base						
15 repair with 6" of 1-1/2 sack cement stabilized sand, 0-50 square	SY	1	\$171.00	\$171.00	\$250.00	\$250.00
Removal, disposal, replacement of concrete and material, base						
16 repair with 6" of 1-1/2 sack cement stabilized sand, 51+ square yards, SY	SY	1	\$123.00	\$123.00	\$255.00	\$255.00
Full Depth Repair of 8 inch Concrete Pavement				\$332.00		\$555.00
Removal, disposal, replacement of concrete and material, base						
17 repair with 6" of 1-1/2 sack cement stabilized sand, 0-50 square	SY	1	\$194.00	\$194.00	\$275.00	\$275.00
Removal, disposal, replacement of concrete and material, base						
18 repair with 6" of 1-1/2 sack cement stabilized sand, 51+ square yards, SY	SY	1	\$138.00	\$138.00	\$280.00	\$280.00
Full Depth Repair of 10 inch Concrete Pavement				\$374.00		\$690.00
Removal, disposal, replacement of concrete and material, base						
19 repair with 6" of 1-1/2 sack cement stabilized sand, 0-50 square	SY	1	\$218.00	\$218.00	\$340.00	\$340.00
Removal, disposal, replacement of concrete and material, base						
20 repair with 6" of 1-1/2 sack cement stabilized sand, 51+ square yards, SY	SY	1	\$156.00	\$156.00	\$350.00	\$350.00
Additional Items				\$4,862.00		\$5,311.25
21 Repair base with 6" of 1-1/2 sack cement stabilized sand, per	SY	1	\$69.00	\$69.00	\$30.50	\$30.50
22 High-early strength concrete, 7-sack, per specifications	SY	1	\$134.00	\$134.00	\$30.75	\$30.75
Install concrete ADA wheelchair ramp with headers,dowels,						
23 expansion joints, and integral color, all types, per specifications	EA	1	\$269.00	\$269.00	\$2,250.00	\$2,250.00
24 Remove and restore inlet box, all types, per specifications	EA	1	\$4,390.00	\$4,390.00	\$3,000.00	\$3,000.00
<b>Base Bid Total:</b>				<b>\$7,258.00</b>		<b>\$10,115.25</b>